

1175 CHURCH STREET • BOHEMIA, LONG ISLAND, NEW YORK 11716 AREA CODE 631 589-6300

> 23 March 2021 416365-00-L18-0925, Revision A

LN1 67 Mariner Drive Southampton, NY 11968

Attention:	Mr. Christopher Gray (Christopher@nillbuildingsolutions.com)			
Subject:	Tensile Strength of Anchor Assemblies			
References:	 (a) LN1 Purchase Order No.: 1805001 (b) Dayton T. Brown, Inc. Quote No.: 18-0861 (c) ASTM D1761-12 			
Enclosures:	 Drawings - 2 Pages Tensile Data - 7 Pages Test Equipment List - 1 Page Photographs - 4 Pages 			

Mr. Gray,

This report, which consists of two pages and four enclosures, presents the results of tensile testing of Anchor Assemblies under reference (a) in accordance with (IAW) reference (b). The test items were received 11 June 2018 and testing was completed 14 June 2018. The reason for this Revision A is to add product codes to the configuration descriptions, which were provided by the customer, in the report.

A total of 21 test items (7 configurations, 3 samples per configuration) were assembled IAW Drawing 416365-3-110, Revision 1 (Enclosure 1) by LN1 and provided to DTB for testing. The tensile testing was performed on an Instron Universal Tensile Tester, Model 5569 with an 11,240-lbf load cell. A test fixture was assembled and installed IAW Drawing 416365-2-001, Revision 1. Testing was performed using the loading procedures outlined in reference (c). Each test item was aligned in the test fixture and attached to the crosshead with a suitably sized bolt. The load was applied by moving the crosshead at a uniform rate of 0.10 in/min until failure. Each test was video recorded. The maximum load and crosshead extension at max load were recorded.

A summary of the average tensile properties of each configuration is provided in Table 1 and the complete results are provided in Enclosure 2. It was observed that all test items failed by withdrawal of the fastener through the wood. No failures were observed in the anchor assemblies or fasteners.



Configuration	Average Maximum Load (lbf)	Average Extension at Max. Load (in)	
NB4 with King Insert (Aluminum Raised with King Insert)	2,933.49	0.14	
NB4 (Aluminum Raised)	3,211.61	0.15	
NB1C (Flush Anchor, 3/4 in Bolt)	1,937.84	0.56	
NB1 (Flush Anchor, 1/2 Bolted from Underneath)	4,003.76	0.17	
NB1AC (Lightning, 5x5)	2,057.00	0.60	
NB3 (Small Anchor Flange Flush)	2,083.34	0.15	
NB2 (Small Anchor Flange Raised)	2,111.88	0.14	

Table 1. Summary of tensile test data.

The test items completed all phases of testing. The test results recorded in this report relate only to those items tested. This test report shall not be reproduced, except in full, without written approval of Dayton T. Brown, Inc.

If you have any questions, please do not hesitate to contact the undersigned at (631) 589-6300 Ext. 4571.

Very truly yours,

DAYTON T. BROWN, INC.

V Londuchtle

Donald Landwehrle for Michael Hemphill Project Engineer

(|th///

Warren Halbig Department Manager

MH:rb

cc: Mr. Lance Nill (lancenillinc@yahoo.com)



Drawings

18-0925A





18-0925A Enc 1 Pg 2



Tensile Data



NB4 with King Insert (Aluminum Raised with King Insert)

Test date: Tuesday, June 12, 2018

RB 3/18/21

Specimen 1 to 3



	Maximum Load (lbf)	Extension at Maximum Load (in)	
1	2718.45	0.14	
2	2877.49	0.14	
3	3204.52	0.16	
Mean	2933.49	0.14	



NB4 (Aluminum Raised) RB 3/18/21

Specimen 1 to 3



	Maximum Load (lbf)	Extension at Maximum Load (in)	
1	3135.26	0.09	
2	2528.42	0.12	
3	3971.13	0.23	
Mean	3211.61	0.15	



NB1C (Flush Anchor 3/4 Inch Bolt) RB 3/18/21

Specimen 1 to 3



	Maximum Load (lbf)	Extension at Maximum Load (in)	
1	1933.85	0.51	
2	1845.61	0.59	
3	2034.05	0.58	
Mean	1937.84	0.56	



NB1 (Flush Anchor, 1/2 Bolted from Underneath) Flush Anchor Half Inch Bolt

RB 3/18/21

Specimen 1 to 3



	Maximum Load (lbf)	Extension at Maximum Load (in)	
1	3903.20	0.14	
2 4194.04		0.19	
3	3914.05	0.19	
Mean	4003.76	0.17	



NB1AC (Lightning 5X5)

RB 3/18/21

Specimen 1 to 3



	Maximum Load (lbf)	Extension at Maximum Load (in)	
1	2537.94	0.66	
2	1707.58	0.56	
3	1925.49	0.57	
Mean	2057.00	0.60	



NB3 (Small Anchor Flange Flush)

RB 3/18/21

Specimen 1 to 3



	Maximum Load (lbf)	Extension at Maximum Load (in)	
1	1991.91	0.10	
2	1948.77	0.14	
3	2309.35	0.20	
Mean	2083.34	0.15	



NB2 (Small Anchor Flange Raised) RB 3/18/21

Specimen 1 to 3



	Maximum Load (lbf)	Extension at Maximum Load (in)	
1	1831.92	0.13	
2	2170.44	0.11	
3	2333.29	0.19	
Mean	2111.88	0.14	



Test Equipment List

18-0925A



Job Sub: 416365-00

TEST EQUIPMENT LIST					
ITEM	MANUFACTURER	MODEL	DTB NO.	ACCURACY	CAL DUE DATE
TESTER, UNIVERSAL TENSILE W/STATIC LOAD CELLS (2)	INSTRON	5569	29-2	$\pm 1\%$ of reading	07/14/2019



Photographs

18-0925A





Photo 1 – Test fixture and setup.



Photo 2 – Test fixture and setup.





Photo 3 – Overview of the NB4 with King Insert (Aluminum Raised with King Insert) configuration.



Photo 4 – Overview of the NB4 (Aluminum Raised) configuration.



DAYTON T. BROWN

Photo 5 – Overview of the NB1C (Flush Anchor, 3/4 in Bolt) configuration.



Photo 6 – Overview of the NB1 (Flush Anchor, 1/2 Bolted from Underneath) configuration.





Photo 7 – Overview of the NB3 (Small Anchor Flange Flush) configuration.



Photo 8 – Overview of the NB2 (Small Anchor Flange Raised) configuration.

18-0925A Enc 4 Pg 4